



MIDNAPORE KHARAGPUR DEVELOPMENT AUTHORITY

(A Statutory Authority of the Government of West Bengal)



Sahid Kshudiram Zilla Parikalpana Bhavan (2nd Floor)

Zilla Parishad Complex, Paschim Medinipur – 721101


Phone No. 03222 – 261739, e-Mail ID : mkdamidnapore@gmail.com

NIQ No. 47 / MKDA/ 2020-21

For and on behalf of MKDA (A statutory body of Government of West Bengal), the Executive Officer MKDA invites sealed quotations / bid from the eligible, bonafide & reputed contractors who are willing to **“Supply & Installtion 45 KVA DG Set of Rani Shiromoni Garh at Karnagarh, Salboni, Paschim Medinipur” (as Per Annexure-I)**, which will be received by E.O., MKDA up to 3:00 pm of 31-12-2020 by hand and will be opened on the same day at 4:00 pm. Midnapore

Terms & Conditions:-

- I. No claim for escalation of rates will be entertained during the currency of the Quotation for idle labour or increase in the cost of labour or materials.
- II. If during execution, the contractor is instructed to carry out any item of altered, additional or substituted work not appearing in the priced schedule attached to the Quotation, the rate for such work will be made on the basis of rates appearing in the schedule of Rates of Public Works (Roads) Department, Govt. of West Bengal, for Midnapur (W) with effective from 01-12-2015, minus/plus the contractual percentage as applicable and if rates for such item do not appear in the PWD (Roads) schedule, the cost of such works will be determined by the Executive Engineer analyzing on the basis of market rates in the line of PWD (Roads) practice in vague.
- III. Brand/company /Grade of materials are to be used for the work shall have to be approved by the Executive Engineer, MKDA, before purchase by the contractor from market.
- IV. General specification and mode of measurement will be as per of the schedule of Rates of Public works Department , Govt. of West Bengal , w.e.f. 01-12-2015
- V. In the event of the Quotation being submitted by a firm, it must be signed separately by each members thereof, or in the event of the absence of any partner; it must be signed on his behalf by a person holding a power of attorney authorizing him to do so.
- VI. The name of the work must be written on the envelope containing the Quotation.
- VII. All materials have to be procured by the contractor from outside and shall have to be approve by the Executive Engineer prior to use in the work.
- VIII. The Contractors are requested to visit the site before quoting rates.
- IX. Work must be completed within specified time period.
- X. Authority reserves the right to reject any or all tenders without assigning any reasons and is not bound to accept the lowest tender.
- XI. In case of the tender whose tender has been accepted and on executing the agreement, the earnest money deposited by him will automatically be converted into security deposit. 2% of the work order amount will be deducted from the 1st RA bill as earnest money and the earnest money deposited along with tender will be released after payment of 1st. RA bill. An amount of 8 % of the value of work executed will deducted from each progressive bill starting from 1st RA bill (10 % in total) will constitute the security deposit. The security deposit will be repaid to the agency (contractor) after 5(five) years for bituminous work & concrete road work, 3(three) years for bituminous repairing work & concrete road repairing work, 1(One) year for building, culvert, drain & bridge etc and 5(five) years for Electrical works, of satisfactory completion of the whole work, in case of failure to complete the work within the stipulated time or in any case of failure to rectify and defect arising during the security period penal measure will be taken and the security deposit will be forfeited and the contractor will be black listed.
- XII. **The amount of Earnest Money of Rs. 5000/- should be deposited in favour of “E- Procurement of MKDA” at UBI Bank A/c No – 0788012026613 (IFSC Code No:UTBIOSPBC34), specifying the name of tenderer and NIQ Number in the Paying Slip through RTGS / NEFT / CBS System / Directly deposit on account only.**
(The Accepted Bidder must deposit Earnest Money within 3 (three) days from the issue of intimation letter.)



Executive Officer, MKDA &
ADM, Paschim Medinipur

Memo No. : 4067 (11) / Engg-342 / MKDA / 20

Date: 23 / 12 / 2020

Copy for kind information to:

1. The Chairman, MKDA
2. The District Magistrate, Paschim Medinipur
3. The ADM & DL&LRO, Paschim Medinipur
4. Additional Executive Officer, Paschim Medinipur Zilla Parishad for wide publication.
5. The SDO, Midnapore Sadar
6. The Executive Engineer, Paschim Medinipur Zilla Parishad for wide publication.
7. The District Information Officer, Paschim Medinipur for wide publication.
8. The Superintendent, Salboni Super Speciality Hospital
9. The Administrator/ Midnapore/Kharagpur Municipality for wide publication.
10. CA to ADM (Dev), Paschim Medinipur for wide publication.
11. Office Notice Board / Guard File.


Executive Officer, MKDA &
ADM, Paschim Medinipur

Annexure-I

Supply & Installtion 45 KVA DG Set of Rani Shiromoni Garh at Karnagarh,Paschim Medinipur			
SI No.	Description of work	Qty.	Unit
1	<p>Supply, Installation, Testing and Commissioning of silent type 45KVA DG set confirming to CPCB -II norms as per the following specification.</p> <p>A.) Diesel Engine : Liquid Cooled Diesel Engine, developing 171/156 BHP at 1500 rpm having blower fan of adequate capacity, fanguard, fan belts etc. the Diesel Engine shall be vertical, Electric start, compression ignition, 4 stocke, continuous run at 1500 rpm confirming to IS 10002, ISO-3046, BS 5514 standard with an permissible over load capacity of 10% for one hour in 12 hour in every 12 hrs. of operation complying present CPCB norms:</p> <p>B.) Alternator: make Alternator suitable to deliver rated output of 45 KVA at 1500 rpm, 415V , 0.8 PF(lag), 50 Hz, 3 phase , in SPDP enclosure, self excited & self regulated, brushless. The Alternator should be IS: 4722/BS EN 60034-1 & will be suitable for tropical condition having full load efficiency above 90% . Class of insulation shall be</p> <p>C.) Gen set Controller: i.) Having indication/LCD display for lub oil pressure, battery viltage, engine rpm, fuel level in the day tank, engine running hrs. indication, AC current, AC Voltage, AC frequency, AC power metering with suitable CTs for displaying ii.) Safety Alarms for High engine temperature, low lub oil pressure, lowraditor water level, low fuel level, battery high voltage, under/over speed alongwith safety tips for High Engine temperature, low lube oil.</p> <p>D.) With out AMF control panel. E.) Base frame,</p> <p>F.) Fuel Tank having atleast 8 hrs. capacity,</p> <p>G.) 12 necessary E.I. Work. Make : Kiloskar green</p>	1	item